KV Partners LLC

P.O. Box 432, New Boston, NH 03070

(603) 413-6650

MEMORANDUM

To:	Mike Pivero, Road Agent
From:	Mike Vignale, KVPartners, LLC
Project:	Roadway Condition Evaluation
Subject:	Approximate Construction Estimate
Date:	February 5, 2014

MEADOW VIEW DRIVE

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL COSTS
1	Mobilization	1	LS	\$3,000.00	\$3,000
2	Site Preparation	1	LS	\$2,000.00	\$2,000
3	Excavation	0	CY	\$12.00	\$0
4	Reclaimed Base Course	3500	SY	\$1.75	\$6,125
5	Gravel	0	CY	\$16.00	\$0
6	Crushed Gravel	150	CY	\$22.00	\$3,300
7	Hot Bituminous Pavement Base and Surface	800	TON	\$80.00	\$64,000
8	Bituminous Concrete Berm	0	LF	\$3.50	\$0
9	Vegetated Swale	1200	LF	\$6.50	\$7,800
10	Catch Basin - Drain	0	EA	\$2,000.00	\$0
11	6" Underdrain	0	LF	\$20.00	\$0
12	18" HDPE	0	LF	\$35.00	\$0
13	Pipe End Sections	0	EA	\$250.00	\$0
14	Loam and Seed	200	SY	\$2.00	\$400
15	Erosion Control (Project wide)	1	LS	\$1,000.00	\$1,000
16	Traffic Control (Project wide)	1	LS	\$1,000.00	\$1,000
	Miscellaneous (10%)	1	LS	\$8,162.50	\$8,163

	TOTAL:	\$96,788
Engineering and Contingency (10%)		\$9,679
	SAY:	\$106,000
Average Per Foot Cost		\$81.54