

P.O. Box 432, New Boston, NH 03070

MEMORANDUM

To: Mike Pivero, Road Agent

From: Mike Vignale, KVPartners, LLC

Project: Roadway Condition Evaluation

Project: Roadway Condition Evaluation
Subject: Approximate Construction Estimate

Date: March 29, 2022

Gale Village Road (1,450')

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL COSTS
1	Mobilization	1	LS	\$5,000.00	\$5,000
2	Site Preparation	1	LS	\$2,000.00	\$2,000
3	Excavation	0	CY	\$12.00	\$0
4	Reclaimed Base Course	3200	SY	\$2.50	\$8,000
5	Gravel	0	CY	\$22.00	\$0
6	Crushed Gravel	60	CY	\$28.00	\$1,680
7	Hot Bituminous Pavement Base and Surface	750	TON	\$80.00	\$60,000
8	Bituminous Concrete Berm	0	LF	\$7.00	\$0
9	Vegetated Swale	0	LF	\$6.50	\$0
10	Catch Basin	0	EA	\$2,600.00	\$0
11	6" Underdrain	0	LF	\$30.00	\$0
12	18" HDPE	0	LF	\$55.00	\$0
13	Pipe End Sections	0	EA	\$250.00	\$0
14	Loam and Seed	0	SY	\$2.00	\$0
15	Erosion Control (Project wide)	1	LS	\$3,000.00	\$3,000
16	Traffic Control (Project wide)	1	LS	\$4,000.00	\$4,000
	Miscellaneous (10%)	1	LS	\$6,968.00	\$6,968

TOTAL: \$90,648

Contingency (10%) \$9,065

SAY: \$100,000

Average Per Foot Cost \$69

